7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing storm water drains in the northern extension of Malleswaram, Bangalore.

No.	Items of work	Per	Quantity
	Constructing storm water drains including earthwork, surki concrete, stone slabs and cement pointing, etc.—		
1	4″ (1) Storm water drain	R. ft.	20,782
2	4″ (2) Do	"	3,597
3	5″ (3) Do	"	2,070
4	5″ (4) Do	"	2,130
5	6″ (6) Do	"	1,081
6	7″ (8) Do	"	1,048
7	3″ Do	"	1,540
8	Drops stone in surki and pointing with surki, etc.	Each	65
9	Raising sides of drain wherever necessary	Lump sum	
10	Constructing revetment and filling earth in 4th Main road ...	"	
11	Improving the natural drainage in 18th Cross road	"	
12	Constructing Main drain (4′×5′) in 15th Cross road with burnt stone in mortar including earthwork, surki concrete, stone slabs, cement plastering ¾″ thick and cement pointing, etc.	R. ft.	480

N. SUBBA ROW,
Executive Engineer.

KRISHNARAJASAGARA WORKS.

Abstract Notification.

The attention of the public is invited to the publication dated 20th June 1918, on page 561, Part IV of the *Mysore Gazette*, wherein tenders for the supply of charcoal required for use on the North Bank of Krishnarajasagara Works for the period commencing from 1st August 1918 to 31st August 1919, is called for.

B. B. GARUDACHARYA,
Superintending Engineer.

HASSAN DIVISION.

Abstract Notification dated 1918.

The attention of the public is invited to pages 541 and 542 of the 24th issue of the *Mysore Gazette* wherein tenders have been called for for constructing Village Elementary School at Bhuvanhalli, Hassan Taluk.

Dated 14th June 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 20th July 1918, for restoring the Masavanghatta tank, Registered No. 257, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A. M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Masavanghatta tank, Register No. 257, Channarayapatna Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptor rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Masavanghatta Tank, Registered No. 257 of Channarayapatna Taluk.

Items of work	Per	Quantity
Bund R. L. 56'00 Top width 6 feet.		
Jungle clearing	Lump sum	
Earthwork, raising bund including watering and tamping	C. yd.	12,037
Turfing	S. yd.	8,912
New grade stone with bed slab	No.	27
Index stone (New)	"	27
B.M. stones (do)	"	2
Register number and date stones	"	1
Gauge stone	"	1
Breach.		
Baling water	Lump sum	
Clearing silt and sand	C. yd.	2,711
Earth cutting and refilling with watering and tamping	"	188
Earthwork raising bund including watering and tamping	"	3,289
Gravel	"	2,343
Turfing	S. yd.	827
New stone revetment	C. yd.	445
Puddle wall	"	394
Sluices—Sluice No. 1 at R. L. 43'50.		
Earthwork cutting and refilling	C. yd.	100
Earthwork cutting	"	20
Surki concrete	C. ft.	215
Burnt brick in surki mortar	"	538
Burnt stone slabs 6" thick	S. ft.	69
Burnt gibbet slabs 9" thick	C. ft.	27
Cast iron pipes 9" diameter including carriage and fixing, etc.	R. ft.	36
Surki mortar plastering	Sqr.	5'00
Drilling holes, etc.	Lump sum	
Providing teakwood plug with iron rod	No.	10
New stone work (Rough)	C. yd.	20
Clearing draught, etc.	Lump sum	
Sluice No. 2, at R. L. 43'50.		
As per sluice No. I.	.....	.....
WASTE WEIRS.		
Left waste weir 200' long R. L. 50'00.		
Earthwork approach and draft clearing and using to wing bund	C. yd.	296
Earthwork cutting foundation, etc.	"	516
Concrete in surki	C. ft.	656
Burnt brick in surki	"	823
Burnt stone slab	S. ft.	849
Surki plastering	Sqr.	1'00
Rough stone work new	C. yd.	354
Old stone	"	30
Turfing	S. yd.	20
Right weir 50 feet long at R. L. 50'00.		
Earthwork excavation	C. yd.	168
Concrete in surki	C. ft.	207
Burnt brick in surki	"	336
Burnt stone slab	S. ft.	238
Surki plastering	Sqr.	0'50
Rough stone work new	C. yd.	134
Old stone work	"	10
Turfing	S. yd.	10
Distribution.		
Opening out sluice channel acqueduct and lifting dam	Lump sum	

R. W. SCALDWELL,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

NOTICE.

The attention of the public is invited to the notification calling for tenders published in pages 562 and 563, Part II of the *Mysore Gaztte*, dated 20th June 1918, for "Reconstructing the washed out tunnels on Sagar-Bhatkal road (Avinahalli-Karur road) in the Shimoga District,

V. R. NIJAGAL,
Executive Engine